

SCHOOL DISTRICT OF CLAY COUNTY
CHANGE ORDER NO. 3

SDCC PROJECT NAME: W.E. Cherry Elementary School Panelboard/Switchgear Replacement

SDCC PROJECT NO: C-3-12/13

The Owner authorized the Contractor to make the following change(s) in the contract dated February 21, 2013.

ORIGINAL CONTRACT AMOUNT: \$ 62,840.00
REVISED CONTRACT AMOUNT BY PREVIOUS CHANGE ORDER(S): \$ 39,610.63

Change(s) and reason(s) for this Change Order: Owner requested changes (see attached).

Additional Time needed for this Change Order is Zero (0) calendar days. Contract Substantial Completion date is July 20, 2013. Final Completion date is August 4, 2013.

For these changes: Add to Deduct from the Contract in accordance with the conditions of the Contract the sum of: Six thousand, thirty-three dollars and 03/100.

CURRENT CONTRACT AMOUNT:	<u>\$39,610.63</u>
ADDITION TO CONTRACT:	<u>\$6,033.03</u>
DEDUCTION TO CONTRACT:	<u>\$0.00</u>
REVISED CONTRACT AMOUNT:	<u>\$45,643.66</u>

ARCHITECT/ENGINEER CERTIFICATION: In my considered professional opinion, as Project Architect/Engineer, the prices quoted in this Change Order are both fair and reasonable and in the proper ratio to the cost of the original work contract under benefit of competitive bidding.


Signature: 
Architect

Date: 7/30/13

By execution of this Change Order, the Contractor acknowledges that all issues related to compensation and time have been resolved and payment recited herein is full compensation for the work identified in this Change Order.

ACCEPTED: Signature: 
Contractor

Date: 7/29/13

Signature: 
SDCC Project Manager

Date: 7-30-13

APPROVED: Signature: _____
School Board Chairman

Date: _____

**SCHOOL DISTRICT OF CLAY COUNTY
CHANGE ORDER #3**

SDCC PROJECT NAME: W.E. Cherry Elementary Panelboard/Switchgear Replacement

SDCC PROJECT NUMBER: C-3-12/13

ADDITIONAL INFORMATION:

- | | |
|--|-------------------|
| 1. Labor and materials to remove existing ranch circuit conductors from conduits servicing Boiler 1 and 2. Support conduit system to meet code, reinstall new current carrying conductors and grounds (2) sets of (3) 500 MCM and (1) 1/0 copper THHN conductor. Labor and materials to remove existing feeder conductors from conduits servicing MDP. Support conduit system to meet code, reinstall existing feeder conductors, add grounds (2) sets of (4) 500 MCM and (1) 1/0 copper THHN conductors. Labor and materials to rework existing secondary conductors. Pulling slack cable back from transformer and splicing (2) sets of secondary conductors as needed to make up main breaker in MSB. | \$6,749.18 |
| 2. Credit labor and material for panel 1AC as shown on original contract documents. Existing feeder is correct size and in good shape. | -\$3,073.44 |
| 3. Material and labor to install shunt trip units on the existing 800 amp breakers feeding the boilers. | <u>\$2,357.29</u> |

Total Change Order Amount: \$6,033.03

Addition of Zero (0) days to the Contract.